

**WETLAND PLANT SCHEDULE**

THE FOLLOWING PLANT MATERIAL WAS INSTALLED RANDOMLY AT 2' O.C. THROUGHOUT THE HATCHED AREA ON THE PLAN.

SCIENTIFIC NAME	COMMON NAME	SIZE	SPACING	QUANTITY	HYDROLOGY
<i>Asclepias incarnata</i>	Swamp milkweed	Quarts	2' o.c.	50	Saturated
<i>Aster novae-angliae</i>	New England Aster	2" Plugs	2' o.c.	50	Saturated
<i>Carex stricta</i>	Tussock Sedge	2" Plugs	2' o.c.	50	0-1"
<i>Carex lurida</i>	Lurid sedge	2" Plugs	2' o.c.	50	0-1"
<i>Eupatorium perfoliatum</i>	Boneset	Quarts	2' o.c.	50	Saturated
<i>Eupatorium purpureum</i>	Joe-pye weed	Quarts	2' o.c.	50	Saturated
<i>Iris versicolor</i>	Blue flag	Quarts	2' o.c.	200	0-3"
<i>Hibiscus moscheutos</i>	Swamp Rose Mallow	Quarts	2' o.c.	50	0-3"
<i>Juncus effusus</i>	Soft rush	2" Plugs	2' o.c.	200	0-3"
<i>Lobelia cardinalis</i>	Cardinal flower	Quarts	2' o.c.	50	0-3"
<i>Reitardia virginica</i>	Arrow arum	Quarts	2' o.c.	100	1-6"
<i>Pontederia cordata</i>	Pickereelweed	Quarts	2' o.c.	150	3-6"
<i>Sagittaria latifolia</i>	Duck potato	Quarts	2' o.c.	100	3-6"
<i>Scirpus atrovirens</i>	Dark green bulrush	2" Plugs	2' o.c.	50	0-2"
<i>Scirpus cyperinus</i>	Woolgrass	2" Plugs	2' o.c.	50	0-2"
<i>Scirpus tabernaemontani</i>	Soft stem bulrush	Quarts	2' o.c.	300	3-6"
<i>Vernonia noveboracensis</i>	New York Ironweed	Quarts	2' o.c.	50	Saturated



NUM.	DATE	REVISION

PLAN PREPARED BY:  
**SITE ENGINEERING CONCEPTS, LLC**  
 P.O. BOX 1992  
 SOUTHEASTERN, PA 19399  
 P: 610-240-0450 F: 610-240-0451 E: INFO@SITE-ENGINEERS.COM

PLAN PREPARED FOR:  
**BRYN MAWR COLLEGE**  
 REGIONAL STORMWATER  
 MANAGEMENT BASIN  
 LOWER MERION TOWNSHIP MONTGOMERY COUNTY PENNSYLVANIA  
 DATE: 15 JUNE 2007

**REGIONAL BASIN  
 WETLAND PLANTING**

**SHEET  
 1 OF 1**

SCALE: 1"=40'

